



- Erosion and sediment control Measures:
1. Contractor shall ensure that construction is completed in a controlled manner to contain all sediment and debris from negatively impacting the Mississippi River or adjacent properties.
  2. Contractor shall install all sediment and erosion features as shown on the plan and shall inspect and maintain said features for the duration of the project and to the satisfaction of the Mississippi Valley Conservation Authority (MVCA) and Municipality of Mississippi Mills.
  3. Limits of silt fencing as shown on the plan shall be extended as directed by the Owner, MVCA and/or Municipality of Mississippi Mills as deemed necessary.
  4. The contractor shall complete daily erosion and sediment control inspections of the site and shall implement any additional sediment and erosion protection features as it deems necessary to prevent any dust or debris from reaching the Mississippi River or negatively impacting adjacent properties.
  5. Silt Fencing shall be installed as per OPSP 219.110.

LEGEND:  
Silt Fencing:



SCALE: NTS			
01	Development Permit Subm.	RD	17 OCT 2024
No.	REVISIONS	BY	DATE
OWNER Ottawa Valley Grain Products Inc.			
PROJECT 4361 Appleton Side Road Grain Mill			
DRAWING TITLE EROSION AND SEDIMENT CONTROL PLAN			
DATE			ESC
17 OCT 2024			